BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/03/2014-15 Dated: 27-10-2014

APPROVED TENDER SCHEDULE –'B'

Item No: 4

Name of Work:-Construction of concrete roads in main and cross roads in 3rd phase in ward No:04 of Yelahnka satellite town sub division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri R SATHEESH	
				Rate	Rate in Words
1	KSRRB 300-1. **Earth work excavation** by manual means in **ordinary soil** involving an average **horizontal throw upto 2 meters** and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.MORTH chapter 3. (P.No.152 Item No. 19.1 of PWD SR 2013-14)	Cum	159.25	70.00	Rupees seventy only
2	KSRB 2-2.2 : **Earth work excavation for foundation of buildings,** water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No. KBS 2.1(b) / 2.3.5, (P.No.5 It No. 2.4) 2013-14	Cum	49.00	300.00	Rupees three hundred only
3	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix **M 7.5 withOPC** cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2,(P. No. 12 It No. 4.3 of PWD SR 2013-14)	Cum	36.75	4400.00	Rupees four thousand four hundred only
4	Providing and laying cement concrete using **20mm and down size granite jelly or ready mixed concrete for RCC** works laid in 15 cm thick layers and well compacted including vibrating curing and necessary steel or ply wood or plank centering and form work etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges)	Cum	150.76	5500.00	Rupees five thousand five hundred only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri R SATHEESH	
				Rate	Rate in Words
5	**Lead for Disposal of Debris** shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 7.00 Km Average Weight of Earth 1.28 Ton/Cum	Cum	208.25	105.00	Rupees one hundred five only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64

Accounts Officer